No.	Items of work	Unit	Rs. a. p.	Quantity	Cost
10	Teakwood windows half panelled shutters and half glazed shutters, iron bars, etc., complete.	S.ft.		193	
11	Ventilators with cement Fret-work ...	„		42	
12	Circular ventilators with cement Fret-works complete.	„		14	
13	Teakwood wrought and put up ...	C.ft.		202·00	
14	Roofing with 1st Class Mangalore tiles on 2" x 1" teak reepers complete.	Sqr.		32·22	
15	Flooring with Cuddapah slabs on 3" concrete bed and cement pointing, etc., complete.	„		17·58	
16	Burnt stone slab pillar 1' x 6" with 2 lines dressed and fixing, etc., complete height 10 feet.	Each		8	
17	Cement pointing to basement ..	Sqr.		3·48	
18	Chacolate painting	„		7·03	
19	Teakwood eave board ordinary 9" wide ...	Rft.		311	
20	Teakwood finials to ends of gables ...	Each		4	
21	Ridge tiles set in mortar	Rft.		114	
22	Chunnam border	„		...	
23	Teakwood planks with zinc sheet and gutters, etc., underneath the valley rafter.	„		64	
24	Earth filling to basement	C.yd.		94	

H. F. MARKER,
Executive Engineer.

MYSORE DIVISION.

Abstract Notification, dated 20th February 1933.

CONSTRUCTING A GIRDER BRIDGE ACROSS THE RIVER KABINI AT T.-NARSIPUR.

The attention of the public is drawn to notification calling for tenders for the above work in pages 215 to 223 of Part VI of the *Mysore Gazette*, dated 23rd February 1933.

The last date of receiving the tenders has been extended upto 3 P.M. on the 20th March 1933.

K. RANGASWAMY IYENGAR,
Executive Engineer.

OFFICE OF THE EXECUTIVE ENGINEER, BHADRA RESERVOIR PROJECT.

Notification dated 11th March 1933.

The Office of the Executive Engineer, Bhadra Reservoir Project, will be shifted from Tarikere to Hassan, from the 15th instant. All communications may be addressed to Hassan

B. KRISHNA RAO,
Executive Engineer.

TUMKUR DIVISION.

Abstract Notification dated 3rd March 1933.

Subject:—Constructing a Primary School Building at Kallur in Gubbi Taluk.

Attention of the public is drawn to notification calling for tenders for the above work in pages 259 to 260 of Part VI of the *Mysore Gazette*, dated 9th March 1933.

The tenders will be received by the Executive Engineer, Tumkur Division, Tumkur, upto 3 P.M. of 30th March 1933.

An earnest money of Rs. 175 should accompany the tender.

Notification, dated 6th March 1933.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Tumkur Division, up to 3 P.M., on 10th April 1933, for "Construction of a Rural Dispensary Building at Honnudike in Tumkur Taluk." An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed before the end of June 1934.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Tumkur, between the hours of 11 A.M. and 5 P.M. on working days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed both in words and figures.

4. Each tender must be accompanied by a deposit of Rs. 250 in cash or currency notes as earnest money and be superscribed "Tender for Construction of a Rural Dispensary Building" at Honnudike, Tumkur Taluk, in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, Tumkur Division, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual bond in default of which his tender will be cancelled and earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Percentage rates above or below the estimate amount will not be accepted.

10. No claims for enhanced rates will be entertained on any account after acceptance of tenders.

11. The contractor will be dealt with in terms of the bond for any short progress or delay. In matters of all disputes about rates and measurements, quality of work, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding on the contractor.

12. Rates should be quoted both in words and figures for each item of work and lumpsum provisions are subject to modification as per data worked out during the execution. For individual items of work under lumpsum provisions, the rates tendered for similar items of work will be paid and for other items; the rates as per schedule of rates will be paid at the discretion of the Executive Engineer.

Abstract estimate for Construction of a Rural Dispensary Building at Honnudike in Tumkur Taluk.

Serial No.	Details	Unit	Quantity as per estimate	Rate	
				In figures	In words
	Dispensary.				
1	Earthwork excavating foundation and filling in basement.	C.yds.	59		
2	Stone jelley concrete in mortar ...	C.ft.	265		
3	Burnt size stone or trap in mud filling foundations.	"	1,134		
4	Do hammer dressed with bond stones.	"	960		
5	Burnt brick in clay	"	1,502		
6	Do chunam	"	594		
7	Teakwood doors panelled with silicate painting and fittings complete.	S.ft.	213		
8	Do battened	"	18		
9	Teakwood windows panelled with $\frac{3}{4}$" iron bars, silicate painting and fittings complete.	"	116		
10	Do battened	"	5		

Serial No.	Items of work	Unit	Quantity as per estimate	Rate	
				In figures	In words
11	Burnt stone slabs 6" thick dressed and fixed.	S.ft.	387		
12	Burnt stone slabs 9" thick dressed and fixed.	,,	15		
13	Roofing with 1st Class Mangalore tiles on teak reepers complete.	Sqr.	11·47		
14	Ridge tiles set in mortar and cement pointed.	R.ft.	112		
15	Cut stone pillars with 7" sqr. with base and capital.	Each	8		
16	Teakwood wrought and put up with wood oiling.	C.ft.	89·84		
17	Chunam plastering	Sqr.	46·55		
18	Flooring with 1½" to 2" thick Cuddapah slabs on 3" concrete and cement pointing.	,,	6·04		
19	Cement pointing to basement ...	,,	3·57		
20	Teakwood eave board (9" x 1") plain alround the roof.	R.ft.	197		
21	Chunam borders over roof	,,	87		
22	Binding walls over roof	,,	22		
23	Pukka terrace 9" thick complete ...	Sqr.	1·58		
24	Cornice 9" thick	R.ft.	48		
25	Valley planks 1" thick with zinc sheets including mortar and cement borders.	S.ft.	80		
26	Teakwood ½" planked screen with painting including groove work and door way at end.	,,	56		
27	Providing sinks in dressing and compounding rooms.	L.S.	L.S.		
28	Constructing drains to lead off water ...	,,	,,		
29	Providing and fixing teakwood pegs and planks complete with wood oiling for store ward and compounding rooms.	,,	,,		
30	Teakwood finials 2½' long	Each	2		
31	Do pendents 1½' long ...	,,	12		
32	Chunam mortar moulding in front as per elevation.	L.S.	L.S.		
33	Providing rain water spouts	Each	4		
34	White washing two coats	Sqr.			
35	Providing mortar and pestal ...	L.S.	L.S.		
36	Burnt brick coping with chunam plastering, and white washing complete.	R.ft.	51		
37	Constructing seats in the latrine ...	L.S.	L.S.		
38	Sundry unforseen works	,,	,,		
39	Acquisition of the site	,,	,,		

Notification dated 6th March 1933.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Tumkur Division, up to 3 P.M. of 3rd April 1933 for "Constructing an Urdu School at Mayasandra in Turuvekere Sub-Taluk." An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1933.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Tumkur, between the hours of 11 A.M. and 5 P.M. on working days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed both in words and figures.

4. Each tender must be accompanied by a deposit of Rs. 175 in cash or currency notes as earnest money and be superscribed "Tender for Constructing an Urdu School at Mayasandra in Turuvekere Sub-Taluk," in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Percentage rates above or below the estimate amount will not be accepted.

10. No claims for enhanced rates will be entertained on any account after acceptance of tenders.

11. The contractor will be dealt with in terms of the bond for any short progress or delay. In matters of all disputes about rates and measurements and quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding on the contractor.

12. Rates should be quoted both in words and figures for each item of work and lumpsum provisions are subject to modification as per data worked out during the execution. For individual items of work under lumpsum provision, the rates tendered for similar items of work will be paid and for other items, the rates as per schedule of rates will be paid at the discretion of the Executive Engineer.

Abstract estimate of quantities for constructing an Urdu School Building at Mayasandra in Turuvekere Sub-Taluk.

No.	Items of work	Unit	Quantity	Rate	
				In figures	In words
1	Earthwork excavating foundation and filling in basement.	C.yd.	47		
2	Stone jelley concrete in chunam mortar for foundation.	C.ft.	465		
3	Size stone in clay for foundation and basement including bond stones at 6' apart.	„	1304		
4	Burnt brick in clay for superstructure ...	„	1590		
5	Burnt brick in mortar ...	...	261		
6	Burnt stone slabs 6" thick roughly dressed and fixed.	S.ft.	420		
7	Teakwood wrought and put up including wood oiling complete.	C.ft.	92·40		
8	Roofing with 1st Class Mangalore tiles on teak reepers and wood oiling to reepers complete.	Sqr.	12·62		
9	Ridge tiles set in mortar and painted with cement.	R.ft.	79		
10	Teakwood battened doors with iron clamps and fitting, etc., complete.	S.ft.	39		

No.	Items of work		Quantity	Rate	
				In figures	In words
				Rs.	Rs
11	Teakwood windows with ½ panelled and ½ glazed or expanded metal ¾" round iron bars clamps, fittings, etc., complete.	S.t.	81		
12	Teakwood trellies work with fitting complete	"	9		
13	Perforated brickwork including chunam and plastering complete.	"	41		
14	Flooring with burnt stone slabs 3" x 4" thick roughly dressed the joints and fixed on sand.	Sqr.	6·26		
15	Chunam plastering	"	36·95		
16	Whitewashing 2 coats	"	36·95		
17	Silicate painting 2 coats	"	2·49		
18	Chunam borders over gables roof 9" x 9" and plastering complete.	R.ft.	72		
19	Chunam painting to basement and cement washing.	Sqr.	3·00		
20	Zinc sheets for valleys 3" wide over the teak wood planks 3' wide and ½" thick including wood oiling and putting valley bunds in mortar and cement plastering complete.	R.ft.	56		
21	Teakwood cave boored plain 9" x 1" including chocolate painting and fixing complete.	"	178		
22	Clearing site and levelling ground and filling in basement if, necessary.	Lump	sum		
23	Sundry and unforeseen works such as showing false windows at rear end rooms putting black wall boards in cement mortar, if necessary and providing glass tiles on roof.	Lump	sum		
24	Pergola or pendal.	...	...		
	Burnt stone pillars 6" thick roughly dressed and fixed including cutting groves on top for pendal in front of the building.	S.ft.	150		
25	Putting longitudinal and cross bamboos including nails, ropes and thatties or mats for covering, etc.	Lump	sum		

N. G. KRISHNA IYENGAR,
Executive Engineer.

MISCELLANEOUS DEPARTMENTS.

OFFICE OF THE REGISTRAR OF JOINT STOCK COMPANIES IN MYSORE, BANGALORE.

Dated 9th March 1933.

In the matter of the Mysore Companies Regulation No. VIII of 1917 and Sree Raghunatha Stores, Ltd

NOTICE PERSUANT TO SECTION 172 (2)

It is hereby notified that the District Court, Mysore Division, has by an order dated 15th June 1932, ordered that Sree Raghunatha Stores, Ltd., be wound up under the provisions of the Mysore Companies Regulation.

D. SRINIVASA IYENGAR,
Registrar of Joint Stock Companies in Mysore.